

ESTUDIOS Y DISEÑOS CABLE SAN CRISTOBAL ESTACION ALTAMIRA CARRERA 12 B ESTE				
<i>Abscisa</i>	Estructura	Area	Vomen	Vomen Acumulado
0+000.000	LOSA CONCRETO	1.48	0.00	0.00
	SUBBASE	1.01	0.00	0.00
	SELLO	0.67	0.00	0.00
	RCD	3.63	0.00	0.00
0+010.000	LOSA CONCRETO	1.47	14.75	14.75
	SUBBASE	1.00	10.06	10.06
	SELLO	0.67	6.71	6.71
	RCD	3.61	36.21	36.21
0+020.000	LOSA CONCRETO	1.46	14.65	29.40
	SUBBASE	1.00	9.99	20.05
	SELLO	0.66	6.66	13.36
	RCD	3.58	35.95	72.16
0+021.088	LOSA CONCRETO	1.53	1.63	31.03
	SUBBASE	1.04	1.11	21.15
	SELLO	0.70	0.74	14.10
	RCD	3.75	3.99	76.15
0+029.991	LOSA CONCRETO	1.77	14.65	45.68
	SUBBASE	1.21	9.99	31.15
	SELLO	0.80	6.66	20.76
	RCD	4.34	35.97	112.12
0+030.000	LOSA CONCRETO	1.77	0.02	45.70
	SUBBASE	1.21	0.01	31.16
	SELLO	0.80	0.00	20.77
	RCD	4.34	0.04	112.16
0+040.000	LOSA CONCRETO	1.77	17.70	63.39
	SUBBASE	1.21	12.07	43.22
	SELLO	0.81	8.04	28.81
	RCD	4.35	43.44	155.60
0+050.000	LOSA CONCRETO	1.78	17.75	81.14
	SUBBASE	1.21	12.10	55.32
	SELLO	0.81	8.07	36.88
	RCD	4.36	43.56	199.16

0+060.000	LOSA CONCRETO	1.78	17.80	98.94
	SUBBASE	1.22	12.14	67.46
	SELLO	0.81	8.09	44.97
	RCD	4.38	43.70	242.86
0+070.000	LOSA CONCRETO	1.79	17.86	116.80
	SUBBASE	1.22	12.18	79.64
	SELLO	0.81	8.12	53.09
	RCD	4.39	43.83	286.69
0+080.000	LOSA CONCRETO	1.79	17.91	134.71
	SUBBASE	1.22	12.21	91.85
	SELLO	0.82	8.14	61.23
	RCD	4.40	43.97	330.65
0+090.000	LOSA CONCRETO	1.80	17.97	152.68
	SUBBASE	1.23	12.25	104.10
	SELLO	0.82	8.17	69.40
	RCD	4.42	44.10	374.76
0+100.000	LOSA CONCRETO	2.16	19.79	172.47
	SUBBASE	1.47	13.49	117.59
	SELLO	0.98	8.99	78.39
	RCD	5.30	48.57	423.33
0+110.000	LOSA CONCRETO	1.28	17.19	189.65
	SUBBASE	0.87	11.72	129.31
	SELLO	0.58	7.81	86.21
	RCD	3.14	42.19	465.52
0+120.000	LOSA CONCRETO	1.29	12.84	202.49
	SUBBASE	0.88	8.75	138.06
	SELLO	0.59	5.83	92.04
	RCD	3.16	31.50	497.02
0+125.471	LOSA CONCRETO	1.29	7.07	209.56
	SUBBASE	0.88	4.82	142.88
	SELLO	0.59	3.21	95.25
	RCD	3.18	17.35	514.37

ESTUDIOS Y DISEÑOS CABLE SAN CRISTOBAL ESTACION ALTAMIRA CARRERA 12 A ESTE				
<i>Abscisa</i>	Estructura	Area	Vomen	Vomen Acumulado
0+000.000	LOSA CONCRETO	1.29	0.00	0.00
	SUBBASE	0.88	0.00	0.00
	SELLO	0.59	0.00	0.00
	RCD	3.16	0.00	0.00
0+010.000	LOSA CONCRETO	1.29	12.90	12.90
	SUBBASE	0.88	8.79	8.79
	SELLO	0.59	5.86	5.86
	RCD	3.17	31.65	31.65
0+020.000	LOSA CONCRETO	1.39	13.40	26.29
	SUBBASE	0.95	9.13	17.93
	SELLO	0.63	6.09	11.95
	RCD	3.41	32.89	64.54
0+029.194	LOSA CONCRETO	1.11	11.51	37.80
	SUBBASE	0.76	7.85	25.77
	SELLO	0.51	5.23	17.18
	RCD	2.73	28.24	92.78
0+030.000	LOSA CONCRETO	1.10	0.89	38.69
	SUBBASE	0.75	0.61	26.38
	SELLO	0.50	0.41	17.59
	RCD	2.70	2.19	94.97
0+040.000	LOSA CONCRETO	1.10	11.00	49.69
	SUBBASE	0.75	7.50	33.88
	SELLO	0.50	5.00	22.59
	RCD	2.70	27.00	121.97
0+050.000	LOSA CONCRETO	1.10	11.00	60.69
	SUBBASE	0.75	7.50	41.38
	SELLO	0.50	5.00	27.59
	RCD	2.70	27.00	148.97
0+060.000	LOSA CONCRETO	1.10	11.00	71.69
	SUBBASE	0.75	7.50	48.88
	SELLO	0.50	5.00	32.59
	RCD	2.70	27.00	175.97

0+070.000	LOSA CONCRETO	1.10	11.00	82.69
	SUBBASE	0.75	7.50	56.38
	SELLO	0.50	5.00	37.59
	RCD	2.70	27.00	202.97
0+080.000	LOSA CONCRETO	1.10	11.00	93.69
	SUBBASE	0.75	7.50	63.88
	SELLO	0.50	5.00	42.59
	RCD	2.70	27.00	229.97
0+090.000	LOSA CONCRETO	1.10	11.01	104.70
	SUBBASE	0.75	7.51	71.39
	SELLO	0.50	5.00	47.59
	RCD	2.71	27.03	257.00
0+100.000	LOSA CONCRETO	1.14	11.20	115.90
	SUBBASE	0.78	7.63	79.02
	SELLO	0.52	5.09	52.68
	RCD	2.79	27.48	284.48
0+110.000	LOSA CONCRETO	1.41	12.77	128.67
	SUBBASE	0.96	8.71	87.73
	SELLO	0.64	5.81	58.49
	RCD	3.47	31.35	315.83
0+120.000	LOSA CONCRETO	1.21	13.14	141.81
	SUBBASE	0.83	8.96	96.69
	SELLO	0.55	5.97	64.46
	RCD	2.98	32.25	348.08
0+130.000	LOSA CONCRETO	1.25	12.33	154.14
	SUBBASE	0.85	8.41	105.10
	SELLO	0.57	5.61	70.06
	RCD	3.07	30.27	378.35
0+137.281	LOSA CONCRETO	1.28	9.22	163.37
	SUBBASE	0.87	6.29	111.39
	SELLO	0.58	4.19	74.26
	RCD	3.14	22.64	400.99

**ESTUDIOS Y DISEÑOS CABLE SAN CRISTOBAL
ESTACION ALTAMIRA**

CALLE 43 A SUR

<i>Abscisa</i>	Estructura	Area	Vomen	Vomen Acumulado
0+000.000	LOSA CONCRETO	1.30	0.00	0.00
	SUBBASE	0.88	0.00	0.00
	SELLO	0.59	0.00	0.00
	RCD	3.18	0.00	0.00
0+010.000	LOSA CONCRETO	1.29	12.93	12.93
	SUBBASE	0.88	8.82	8.82
	SELLO	0.59	5.88	5.88
	RCD	3.17	31.75	31.75
0+020.000	LOSA CONCRETO	1.33	13.10	26.03
	SUBBASE	0.91	8.93	17.75
	SELLO	0.60	5.95	11.83
	RCD	3.26	32.14	63.89
0+030.000	LOSA CONCRETO	1.10	12.13	38.16
	SUBBASE	0.75	8.27	26.02
	SELLO	0.50	5.52	17.35
	RCD	2.70	29.78	93.67
0+040.000	LOSA CONCRETO	1.10	11.00	49.16
	SUBBASE	0.75	7.50	33.52
	SELLO	0.50	5.00	22.35
	RCD	2.70	27.00	120.67
0+050.000	LOSA CONCRETO	1.10	11.00	60.16
	SUBBASE	0.75	7.50	41.02
	SELLO	0.50	5.00	27.35
	RCD	2.70	27.00	147.67
0+060.000	LOSA CONCRETO	1.10	11.00	71.16
	SUBBASE	0.75	7.50	48.52
	SELLO	0.50	5.00	32.35
	RCD	2.70	27.00	174.67
0+070.000	LOSA CONCRETO	1.10	11.00	82.16
	SUBBASE	0.75	7.50	56.02
	SELLO	0.50	5.00	37.35
	RCD	2.70	27.00	201.67

0+080.000	LOSA CONCRETO	1.31	12.03	94.20
	SUBBASE	0.89	8.20	64.22
	SELLO	0.59	5.47	42.82
	RCD	3.21	29.53	231.21
0+090.000	LOSA CONCRETO	1.40	13.54	107.73
	SUBBASE	0.96	9.23	73.45
	SELLO	0.64	6.15	48.97
	RCD	3.44	33.23	264.44
0+100.000	LOSA CONCRETO	1.30	13.52	121.25
	SUBBASE	0.89	9.22	82.67
	SELLO	0.59	6.15	55.11
	RCD	3.20	33.18	297.62
0+108.987	LOSA CONCRETO	1.29	11.66	132.91
	SUBBASE	0.88	7.95	90.62
	SELLO	0.59	5.30	60.42
	RCD	3.17	28.63	326.25

**ESTUDIOS Y DISEÑOS CABLE SAN CRISTOBAL
ESTACION ALTAMIRA**

CALLE 42 B SUR

<i>Abscisa</i>	Estructura	Area	Vomen	Vomen Acumulado
<i>0+000.000</i>	LOSA CONCRETO	0.89	0.00	0.00
	SUBBASE	0.67	0.00	0.00
	SELLO	0.45	0.00	0.00
	RCD	2.41	0.00	0.00
<i>0+010.000</i>	LOSA CONCRETO	0.90	8.94	8.94
	SUBBASE	0.67	6.70	6.70
	SELLO	0.45	4.47	4.47
	RCD	2.42	24.13	24.13
<i>0+019.974</i>	LOSA CONCRETO	1.19	10.41	19.35
	SUBBASE	0.89	7.81	14.51
	SELLO	0.60	5.21	9.67
	RCD	3.22	28.11	52.24
<i>0+028.903</i>	LOSA CONCRETO	1.54	12.21	31.55
	SUBBASE	1.16	9.15	23.67
	SELLO	0.77	6.10	15.78
	RCD	4.16	32.96	85.20
<i>0+030.000</i>	LOSA CONCRETO	1.38	1.60	33.16
	SUBBASE	1.03	1.20	24.87
	SELLO	0.69	0.80	16.58
	RCD	3.72	4.32	89.52
<i>0+040.000</i>	LOSA CONCRETO	1.31	13.46	46.61
	SUBBASE	0.99	10.09	34.96
	SELLO	0.66	6.73	23.31
	RCD	3.55	36.33	125.85
<i>0+050.000</i>	LOSA CONCRETO	1.26	12.89	59.50
	SUBBASE	0.95	9.67	44.63
	SELLO	0.63	6.45	29.75
	RCD	3.41	34.81	160.66
<i>0+060.000</i>	LOSA CONCRETO	1.22	12.40	71.90
	SUBBASE	0.91	9.30	53.92
	SELLO	0.61	6.20	35.95
	RCD	3.28	33.47	194.13

0+070.000	LOSA CONCRETO	1.17	11.90	83.80
	SUBBASE	0.87	8.93	62.85
	SELLO	0.58	5.95	41.90
	RCD	3.15	32.14	226.27
0+079.597	LOSA CONCRETO	1.33	11.95	95.76
	SUBBASE	0.99	8.97	71.82
	SELLO	0.66	5.98	47.88
	RCD	3.58	32.28	258.55