













VIGA VC-11						
CANTIDADES DE OBRA PARA 1 ELEMENTOS						
COD	NOMBRE		DIAGRAMA	CANTIDAD UNITARIA	CANTIDAD TOTAL	PESO TOTAL
VL007	6	45		4	4	40,27
VL006	6	90		4	4	80,55
VL007	6	65		4	4	58,17
VL007	6	35		2	2	15,66
VL006	7	55		2	2	33,50
VL007	6	45		2	2	20,14
VL007	6	33		3	3	22,15
VL006	6	75		3	3	50,34
VL007	6	90		3	3	60,41
VL007	6	58		3	3	38,93
VL006	6	100		3	3	67,12
VL007	6	40		3	3	26,85
VL003	4	27		78	78	209,42
VL008	3	10		78	78	43,63
Acero total [kg]						767,15

NOTAS:

- 1-ESTAS CANTIDADES SON TOTALES PARA CADA ELEMENTO
- 2-LOS CUADROS DE HIERROS INDICADOS DEBERÁN SER VERIFICADOS POR EL CONSTRUCTOR ANTES DE LA FIGURACIÓN DE LOS ACEROS DE REFUERZO.
- 3-LOS CUADROS DE CANTIDADES MOSTRADOS SE DEBEN UTILIZAR ÚNICAMENTE COMO REFERENCIA.